





# Regulatory Information Report

## **RIRF24097**

## Fire resistance test for penetrations through a vertical separating element

Client: Agnitek Pty Ltd

Test method: AS1530.4-2014

Report Date: 28/10/2024

Test number: PF24097



## **Table of Contents**

| 1.1   | Document revision schedule                       |
|-------|--|
| 1.2   | Signatories3                                     |
| 2. Re | port Summary4                                    |
| 3. Ge | eneral Information5                              |
| 3.1   | Testing Scope5                                   |
| 3.2   | Contact Details5                                 |
| 3.3   | Specimen Preparation, Conditioning and Timeline6 |
| 3.4   | Use of the Report6                               |
| 4. Sp | ecimen Description7                              |
| 4.1   | Supporting Construction7                         |
| 4.2   | Specimens8                                       |
| 5. Te | st Results12                                     |
| 5.1   | Observations during the test                     |
| 5.2   | Specimen 1                                       |
| 5.3   | Specimen 2                                       |
| 5.4   | Specimen 3                                       |
| 5.5   | Specimen 4                                       |
| 5.6   | Specimen 5                                       |
| 5.7   | Specimen 6                                       |
| 6.8   | Specimen 722                                     |
| 6. Ph | otos   |
| 6.1   | Photos before the test                           |

#### 1.1 Document revision schedule

| Revision # | Date       | Description      |
|------------|------------|------------------|
| 1          | 28/10/2024 | Issued to Client |

## 1.2 Signatories

| Report         | Name                               | Signature | Date       |
|----------------|------------------------------------|-----------|------------|
| Prepared by:   | pared by: Alexey Kokorin           |           | 28/10/2024 |
| Authorised by: | Andrew Bain (Authorized signatory) | Ah-       | 28/10/2024 |



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation

## 2. Report Summary

Service penetration was tested passing through two layers of 13mm FR Plasterboard on each side of a 64mm (nominal) steel frame.

| Specimen<br>#    | Service                             | Actual<br>Integrity<br>(min) | Actual<br>Insulation<br>(min) | FRL       |
|------------------|-------------------------------------|------------------------------|-------------------------------|-----------|
| 1                | AGNI-Box – empty                    | 124NF                        | 124NF                         | -/120/120 |
| 2                | AGNI-Box – filled                   | 124NF                        | 92                            | -/120/90  |
| 2a               | 3 x Pair Coil with FR<br>Insulation | 124NF                        | 92                            | -         |
| 2b               | 3 x 20mm Condensate Pipes           | 124NF                        | 124NF                         | -         |
| 2c               | 25 x TPS Cables                     | 124NF                        | 124NF                         | -         |
| 3                | AGNI-Box – filled                   | 124NF                        | 73                            | -/120/60  |
| 3a               | 50mm Steel Pipe                     | 124NF                        | 73                            | -         |
| 3b               | 25 x Alarm Cables                   | 124NF                        | 114                           | -         |
| 3c               | 3c 25 x Data Cables                 |                              | 102                           | -         |
| 4                | AGNI-Box – filled                   | 124NF                        | 9                             | -/120/-   |
| 4a               | 32mm PEX/AL/PEX Pipe                | 124NF                        | 9                             | -         |
| 4b               | 4b 16mm PEX/AL/PEX Pipe             |                              | 11                            | -         |
| 4c 40mm PEX Pipe |                                     | 124NF                        | 12                            | -         |
| 4d               | 4d 16mm PEX Pipe                    |                              | 12                            | -         |
| 5                | DN32 PVC-U Pipe                     | 124NF                        | 124NF                         | -/120/120 |
| 6                | DN25 PEX Pipe                       | 124NF                        | 124NF                         | -/120/120 |
| 7                | DN40 PEX Pipe                       | 124NF                        | 46                            | -/120/45  |

NF - No failure during the test

#### 3. General Information

#### 3.1 Testing Scope

#### **Applicable Standards:**

AS 1530.4-2014 Section 10: Service penetrations and control joints

AS 4072.1-2005 (r. 2016) Components for the protection of openings in fire-resistant separating elements. Part 1: Service penetrations and control joints

#### **Departures from Testing Method:**

No departures from the testing method

#### **Test conditions:**

Conditions complied with the Standard

#### 3.2 Contact Details

#### **Accredited Testing Laboratory**

Fire TS Lab - Passive Fire Inspection and Test Services Ltd

Accreditation Number - 1335

1/113 Pavilion Drive, Mangere, Auckland, 2022

New Zealand

Contact e-mail: tests@firelab.co.nz

#### **Client/Applicant:**

Agnitek Pty Ltd

8 Clare St, Bayswater, VIC, 3153

Australia

Contact e-mail: <a href="mailto:info@agnitek.com.au">info@agnitek.com.au</a>

#### Manufacturer:

Same as Client/Applicant

#### 3.3 Specimen Preparation, Conditioning and Timeline

#### Specimens conditioning and delivery to Laboratory:

Separating element was built by the Laboratory in line with Client instructions. Installation of fire stopping system was performed by the Laboratory in line with Client instructions. The Laboratory was not involved in sampling of the materials. The Laboratory checked materials during construction of the specimen. All services (except for empty AGNI-Boxes) we capped on the fire side only.

Testing date: Installation completion date:

10/09/2024 05/09/2024

#### **Termination of The Test:**

The test was discontinued at 124 minutes.

#### 3.4Use of the Report

This report shall not be reproduced, except in full.

A regulatory information report was issued in addition to the full test report PF24097. This provides the minimum information required for regulatory compliance.

This report details the methods of construction, test conditions and the results obtained when the specific element of construction described herein was tested following the procedure outlined in AS 1530.4. Any significant variation with respect to size, constructional details, loads, stresses, edge or end conditions, other than that allowed under the field of direct application in the relevant test method, is not covered by this report.

Because of the nature of fire resistance testing and the consequent difficulty in quantifying the uncertainty of measurement of fire resistance, it is not possible to provide a stated degree of accuracy of the result.

The test results relate to the specimens of the product in the form in which they were tested. Differences in the composition or thickness of the product may significantly affect the performance during the test and may therefore invalidate the test results. Care should be taken to ensure that any product, which is supplied or used, is fully represented by the specimens, which were tested.

The specimens were supplied by the sponsor and the Laboratory was not involved in any of selection or sampling procedures.

The results of these fire tests may be used to directly assess fire hazard, but it should be recognized that a single test method will not provide a full assessment of fire hazard under all fire conditions.

## 4. Specimen Description

## 4.1 Supporting Construction

| Separating element |            |  |
|--------------------|------------|--|
| 1.1                | Item       | 64mm (nominal) steel stud frame with two layers of 13mm FR Plasterboard fitted to each side of the frame |
|                    | Dimensions | Width / Height (W/H): 1200mm × 1200mm  |

| Materi | Materials           |   |  |  |
|--------|---------------------|---|--|--|
| 1.3    | Item / Product Name | Steel Stud  |  |  |
|        | Dimensions          | Width / Height (W/H): 64mm x 1200mm   |  |  |
|        | Installation        | Used to construct studs in steel frame and nogs                             |  |  |
| 1.4    | Item / Product Name | Steel Track   |  |  |
|        | Dimensions          | Width / Height (W/H): 64mm x 1200mm   |  |  |
|        | Installation        | Used to construct top and bottom plates in steel frame                      |  |  |
| 1.5    | Item / Product Name | Self-Tapping Screw  |  |  |
|        | Dimensions          | 10g x 16mm  |  |  |
|        | Installation        | Used to construct steel stud frame – secure studs, tracks and nogs together |  |  |
| 1.6    | Item / Product Name | FR plasterboard   |  |  |
|        | Dimensions          | Width / Height (W/H): 1200mm x 1200mm                                       |  |  |
|        |                     | Thickness (T): 13mm   |  |  |
|        | Installation        | Two layers applied to each face of the frame to create separating element   |  |  |
| 1.7    | Item / Product Name | Self Tapping Screw  |  |  |
|        | Dimensions          | 41mm  |  |  |
|        | Installation        | Used to secure GIB Fyreline to frame  |  |  |

## 4.2 Specimens

| Servic | Services            |   |  |  |
|--------|---------------------|---|--|--|
| 2.1    | Item / Product Name | AGNI-Box  |  |  |
|        | Dimensions          | Width / Height (W/H): 300mm x 151mm   |  |  |
|        | Construction        | The AGNI-Box is constructed using 1.0 BMT steel measuring 300mm (width) x 151mm (height) x 200mm (depth). A 50mm recessed steel lip surrounds all four side of both faces of the AGNI-Box and holds two layers of 3.5mm intumescent. The recessed space on both faces of the AGNI-Box was fitted with 50mm thick foam, friction fit into the frame. |  |  |
| 2.2    | Item / Product Name | FR RUBBER INSULATED PAIR COIL   |  |  |
|        | Copper Pipe 1       | Diameter (OD): 9.52mm   |  |  |
|        |                     | Diameter (ID): 7.9mm  |  |  |
|        |                     | Thickness (T): 0.81mm   |  |  |
|        | Copper Pipe 2       | Diameter (OD): 15.88mm  |  |  |
|        |                     | Diameter (ID): 13.84mm  |  |  |
|        |                     | Thickness (T): 1.02mm   |  |  |
|        | Insulation          | Wall Thickness (T): 19mm  |  |  |
|        |                     | Material: Nitrile Butadiene Rubber  |  |  |
|        | Location            | 3 included in specimen 2  |  |  |
| 2.3    | Item / Product Name | uPVC ELECTRICAL CONDUIT 25mm  |  |  |
|        | Dimensions          | Diameter (OD): 25mm   |  |  |
|        |                     | Diameter (ID): 21mm   |  |  |
|        |                     | Thickness (T): 2mm  |  |  |
|        | Location            | 3 included in specimen 2  |  |  |
| 2.4    | Item / Product Name | ELECTRICAL CABLE 450/750V 2C + E  |  |  |
|        | Cable Dimensions    | Width x Depth (W/D): 14mm x 6.5mm   |  |  |
|        | Core Dimensions     | Overall Diameter (OD): 4mm  |  |  |
|        |                     | Wire Diameter: 0.85mm   |  |  |
|        | Earth Dimensions    | Overall Diameter (OD): 3.2mm  |  |  |
|        |                     | Wire Diameter: 0.64mm   |  |  |

|      | Location            | 25 included in specimen 2            |
|------|---------------------|--------------------------------------|
| 2.5  | Item / Product Name | 50mm STEEL PIPE                      |
|      | Dimensions          | Diameter (OD): 48.5mm                |
|      |                     | Diameter (ID): 40.5mm                |
|      |                     | Thickness (T): 4mm                   |
|      | Location            | 1 included in specimen 3             |
| 2.6  | Item / Product Name | 2 C 0.75mm² RED FIRE ALARM CABLE TCW |
|      | Dimensions          | Overall Diameter (OD): 6.5mm         |
|      | Location            | 25 included in specimen 3 – AGNI-Box |
| 2.7  | Item / Product Name | CAT6 CABLE                           |
|      | Dimensions          | Overall Diameter (OD): 7.5mm         |
|      | Location            | 25 included in specimen 3            |
| 2.8  | Item / Product Name | DN16 SDR9 PEX PIPE                   |
|      | Dimensions          | Diameter (OD): 16mm                  |
|      |                     | Diameter (ID): 11mm                  |
|      |                     | Thickness (T): 2.5mm                 |
|      | Location            | 1 included in specimen 4             |
| 2.9  | Item / Product Name | DN40 SDR11 PE-X PIPE                 |
|      | Dimensions          | Diameter (OD): 40mm                  |
|      |                     | Diameter (ID): 28mm                  |
|      |                     | Thickness (T): 6mm                   |
|      | Location            | 1 included in specimen 4, specimen 7 |
| 2.10 | Item / Product Name | DN20 PE-X/AL/PE-X PIPE               |
|      | Dimensions          | Diameter (OD): 20mm                  |
|      |                     | Diameter (ID): 16mm                  |
|      |                     | Thickness (T): 2mm                   |
|      | Location            | 1 included in specimen 4             |
| 2.11 | Item / Product Name | DN32 PE-X/AL/PE-X PIPE               |
|      | Dimensions          | Diameter (OD): 32mm                  |
|      |                     | Diameter (ID): 26mm                  |
|      |                     | Thickness (T): 3mm                   |

|      | Location            | 1 included in specimen 4 |
|------|---------------------|--------------------------|
| 2.12 | Item / Product Name | DN32 PVC-U DWV PIPE      |
|      | Dimensions          | Diameter (OD): 36mm      |
|      |                     | Diameter (ID): 32mm      |
|      |                     | Thickness (T): 2mm       |
|      | Location            | 1 included in specimen 5 |
| 2.13 | Item / Product Name | DN25 SDR9 PEX PIPE       |
|      | Dimensions          | Diameter (OD): 25.5mm    |
|      |                     | Diameter (ID): 18.5mm    |
|      |                     | Thickness (T): 3.5mm     |
|      | Location            | 1 included in specimen 6 |

| Sealants |                     |               |
|----------|---------------------|---------------|
| 3.1      | Item / Product Name | AGNI-Seal     |
|          | Dimensions          | 600mL Sausage |

| Fixings |                     |  |  |  |
|---------|---------------------|--|--|--|
| 4.1     | Item / Product Name | Self-Tapping Screw                     |  |  |
|         | Dimensions          | 41mm                                   |  |  |
|         | Installation        | Used to secure AGNI-Box to steel frame |  |  |
| 4.2     | Item / Product Name | Self-Tapping Screw                     |  |  |
|         | Dimensions          | 10g x 16mm                             |  |  |
|         | Installation        | Used to construct AGNI-Box steel frame |  |  |

| Intumescent |              |  |  |  |
|-------------|--------------|--|--|--|
| 5.1         | Item         | AGNI-Wrap 50                                     |  |  |
|             | Dimensions   | Width (W): 50mm                                  |  |  |
|             |              | Thickness (T): 3.5mm                             |  |  |
|             | Installation | Installed around services in specimen 5, 6 and 7 |  |  |

| Other |                     |                                     |
|-------|---------------------|-------------------------------------|
| 6.1   | Item / Product Name | Steel Stud 64mm 0.55bmt             |
|       | Dimensions          | Width / Height (W/H): 300mm x 151mm |
|       | Installation        | Used to frame AGNI-Box              |

## 5. Test Results

### 5.1 Observations during the test


| Time<br>min | Test<br>face | SP#           | OBSERVATIONS/REMARKS                                |
|-------------|--------------|---------------|---|
| 1           | U            | 2, 3,<br>4    | Smoke coming out from around services               |
| 4           | U            | 1             | Smoke coming out from the specimen                  |
| 7           | U            | 4             | Foam pushing out from face of AGNI-Box              |
| 9           | U            | 1             | Foam fallen out of AGNI-Box. Cotton pad test – PASS |
| 37          | U            | 5, 6          | Smoke coming out from between pipe and SE           |
| 40          | U            | 1, 2,<br>3, 4 | Sealant cone beginning to bubble and expand         |
| 46          | U            | 7             | Sealant expanding, pipe beginning to distort        |
| 60          | U/E          | All           | No major observations                               |
| 124         |              |               | TEST DISCONTINUED                                   |

NOTE: E - Exposed Face (inside furnace)

U - Unexposed Face (outside furnace)

SE - Separating element

## 5.2 Specimen 1




| Service penetration details |                    |
|-----------------------------|--------------------|
| Service                     | AGNI-Box           |
| Aperture Size               | 300mm x 151mm      |
| Annular Spacing             | Min: 0mm, Max: 5mm |

| Local Fire-stopping system |   |  |
|----------------------------|---|--|
| Application                | Symmetrical – applied to both faces of separating element   |  |
| System description         | The following procedure was followed:   |  |
|                            | 64mm steel stud frame was constructed (300mm wide x 151mm height) in the centre of the cavity for a tight fit of the AGNI-Box.                          |  |
|                            | AGNI-Box was secured to the steel stud frame using 41mm screws on all four sides of the AGNI-Box.   |  |
|                            | A 40mm x 40mm AGNI-Seal cone was applied between the AGNI-Box and the separating element. The AGNI-Seal cone surrounded all four edges of the AGNI-Box. |  |

| Test results        |                           |  |
|---------------------|---------------------------|--|
| Structural adequacy | Not applicable            |  |
| Integrity           | No failure at 124 minutes |  |
| Insulation          | No failure at 124 minutes |  |

## 5.3 Specimen 2



| Service penetration details |   |
|-----------------------------|---|
| Service                     | AGNI-Box – filled (3 x FR Pair Coil, 25 x TPS Cables and 3 x uPVC Electrical Conduit Pipes) |
| Aperture Size               | 300mm x 151mm   |
| Annular Spacing             | Min: 0mm, Max: 5mm  |


| Local Fire-stopping system |   |  |
|----------------------------|---|--|
| Application                | Symmetrical – applied to both faces of separating element   |  |
| System description         | <ol> <li>The following procedure was followed:</li> <li>64mm steel stud frame was constructed (300mm wide x 151mm height) in the centre of the cavity for a tight fit of the AGNI-Box.</li> <li>AGNI-Box was secured to the steel stud frame using two 41mm screws on all four sides of the AGNI-Box.</li> <li>A 40mm x 40mm AGNI-Seal cone was applied between the AGNI-Box and the separating element. The AGNI-Seal cone surrounded all four edges of the AGNI-Box.</li> <li>The services were inserted into the AGNI-Box – 3 x pair coils grouped together in the left position, 25 cables bundled together in the centre position and 3 pipes</li> </ol> |  |

- grouped together in the right position. These services were lightly touching each other to fit in the AGNI-Box.
- 5. The foam was cut in half horizontally and then was cut to friction fit around the services.
- 6. The foam was then inserted into the face of the AGNI-Box.

| Test results - specimen |                           |  |
|-------------------------|---------------------------|--|
| Structural adequacy     | Not applicable            |  |
| Integrity               | No failure at 124 minutes |  |
| Insulation              | 92 minutes                |  |

| 2a | 3 x Pair Coil with FR Insulation | 124NF | 92    |
|----|----------------------------------|-------|-------|
| 2b | 3 x 20mm Condensate Pipes        | 124NF | 124NF |
| 2c | 25 x TPS Cables                  | 124NF | 124NF |

## 5.4 Specimen 3



| Service penetration details |  |
|-----------------------------|--|
| Service                     | AGNI-Box – filled (50mm Steel Pipe, 25 x Alarm Cables, 25 x Data Cables) |
| Aperture Size               | 300mm x 151mm  |
| Annular Spacing             | Min: 0mm, Max: 5mm   |


| Local Fire-stopping system   |  |  |
|--|--|--|
| Symmetrical – applied to both faces of separating element  |  |  |
| <ol> <li>The following procedure was followed:</li> <li>64mm steel stud frame was constructed (300mm wide x 151mm height) in the centre of the cavity for a tight fit of the AGNI-Box.</li> <li>AGNI-Box was secured to the steel stud frame using two 41mm screws on all four sides of the AGNI-Box.</li> <li>A 40mm x 40mm AGNI-Seal cone was applied between the AGNI-Box and the separating element. The AGNI-Seal cone surrounded all four edges of the AGNI-Box.</li> <li>The services were inserted into the AGNI-Box – steel pipe in the left position, 25 alarm cables bundled together in the centre position and 25 data cables bundled together in the right position. These services</li> </ol> |  |  |
|  |  |  |

| were spaced 30mm (nominal) apart from e | each other in |
|---|---------------|
| the AGNI-Box.                           |               |

- 5. The foam was cut in half horizontally and then was cut to friction fit around the services.
- 6. The foam was then inserted into the face of the AGNI-Box.

|                  | Test results - sp | ecimen              |                           |  |
|------------------|-------------------|---------------------|---------------------------|--|
| Structural adequ | uacy              | Not applicable      |                           |  |
| Integrity        |                   | No failure at 124 r | No failure at 124 minutes |  |
| Insulation       |                   | 73 minutes          | 73 minutes                |  |
|                  |                   |                     |                           |  |
| 3a               | 50mm Steel Pipe   | 124NF               | 73                        |  |
| 3b               | 25 x Alarm Cables | 124NF               | 114                       |  |
| 3c               | 25 x Data Cables  | 124NF               | 102                       |  |

## 5.5 Specimen 4



| Service penetration details |  |
|-----------------------------|--|
| Service                     | AGNI-Box – filled (16mm PEX Pipe, 40mm PEX Pipe, 20mm PE-X/AL/PE-X Pipe, 32mm PE-X/AL/PE-X Pipe) |
| Aperture Size               | 300mm x 151mm  |
| Annular Spacing             | Min: 0mm, Max: 5mm   |


| Local Fire-stopping system |  |  |
|----------------------------|--|--|
| Application                | Symmetrical – applied to both faces of separating element  |  |
| System description         | <ol> <li>The following procedure was followed:</li> <li>64mm steel stud frame was constructed (300mm wide x 151mm height) in the centre of the cavity for a tight fit of the AGNI-Box.</li> <li>AGNI-Box was secured to the steel stud frame using two 41mm screws on all four sides of the AGNI-Box.</li> <li>A 40mm x 40mm AGNI-Seal cone was applied between the AGNI-Box and the separating element. The AGNI-Seal cone surrounded all four edges of the AGNI-Box.</li> <li>The services were inserted into the AGNI-Box – 32mm PEX/AL/PEX pipe in the left position, 16mm PEX/AL/PEX pipe in the centre-left position, 40mm PEX pipe in the centre-right pipe and 16mm PEX pipe in the</li> </ol> |  |
|                            | right position. These services were spaced 20mm – 40mm (nominal) apart from each other in the AGNI-Box.  |  |

- 5. The foam was cut in half horizontally and then was cut to friction fit around the services.
- 6. The foam was then inserted into the face of the AGNI-Box.

| Test results        |                           |
|---------------------|---------------------------|
| Structural adequacy | Not applicable            |
| Integrity           | No failure at 124 minutes |
| Insulation          | 9 minutes                 |

| 4a | 32mm PEX/AL/PEX Pipe | 124NF | 9  |
|----|----------------------|-------|----|
| 4b | 16mm PEX/AL/PEX Pipe | 124NF | 11 |
| 4c | 40mm PEX Pipe        | 124NF | 12 |
| 4d | 16mm PEX Pipe        | 124NF | 12 |

## 5.6 Specimen 5




| Service penetration details |                    |
|-----------------------------|--------------------|
| Service                     | DN32 PVC-U Pipe    |
| Aperture Diameter           | 46mm               |
| Annular Spacing             | Min: 4mm, Max: 6mm |

| Local Fire-stopping system |   |  |
|----------------------------|---|--|
| Application                | Symmetrical – applied to both face of the separating element  |  |
| System description         |   |  |
|                            | 50mm thick AGNI-Wrap was cut to fit one revolution of the circumference of the aperture.      The AGNI Wrap and the little of the aperture of the aperture. |  |
|                            | <ol><li>The AGNI-Wrap was inserted into the aperture, finishing<br/>10mm past the separating element.</li></ol>   |  |
|                            | <ol><li>5mm (nominal) bead of AGNI-Seal was used applied<br/>between the AGNI-Wrap and the separating element.</li></ol>                                    |  |
|                            | <ol> <li>The gap between the AGNI-Wrap and the pipe was filled<br/>with AGNI-Seal 10mm (nominal) deep.</li> </ol>   |  |

| Test results        |                           |
|---------------------|---------------------------|
| Structural adequacy | Not applicable            |
| Integrity           | No failure at 124 minutes |
| Insulation          | No failure at 124 minutes |

## 5.7 Specimen 6




| Service penetration details |                      |
|-----------------------------|----------------------|
| Service                     | DN25 SDR9 PEX PIPE   |
| Aperture Diameter           | 36mm                 |
| Annular Spacing             | Min: 4mm, Max: 6.5mm |

| Local Fire-stopping system |  |  |
|----------------------------|--|--|
| Application                | Symmetrical – applied to both face of the separating element   |  |
| System description         | The following procedure was followed:  |  |
|                            | <ol> <li>50mm thick AGNI-Wrap was cut to fit one revolution of the circumference of the aperture.</li> <li>The AGNI-Wrap was inserted into the aperture, finishing 10mm past the separating element.</li> <li>5mm (nominal) bead of AGNI-Seal was used applied between the AGNI-Wrap and the separating element.</li> <li>The gap between the AGNI-Wrap and the pipe was filled with AGNI-Seal 10mm (nominal) deep.</li> </ol> |  |

| Test results        |                           |
|---------------------|---------------------------|
| Structural adequacy | Not applicable            |
| Integrity           | No failure at 124 minutes |
| Insulation          | No failure at 124 minutes |

## 6.8 Specimen 7



| Service penetration details |                        |
|-----------------------------|------------------------|
| Service                     | DN40 SDR11 PEX PIPE    |
| Aperture Diameter           | 50mm                   |
| Annular Spacing             | Min: 4.5mm, Max: 5.5mm |

| Local Fire-stopping system |   |  |
|----------------------------|---|--|
| Application                | Symmetrical – applied to both face of the separating element  |  |
| System description         | The following procedure was followed:   |  |
|                            | <ol> <li>50mm thick AGNI-Wrap was cut to fit one revolution of the circumference of the aperture.</li> <li>The AGNI-Wrap was inserted into the aperture, finishing 10mm past the separating element.</li> </ol>           |  |
|                            | <ol> <li>5mm (nominal) bead of AGNI-Seal was used applied between the AGNI-Wrap and the separating element.</li> <li>The gap between the AGNI-Wrap and the pipe was filled with AGNI-Seal 10mm (nominal) deep.</li> </ol> |  |

| Test results        |                           |  |
|---------------------|---------------------------|--|
| Structural adequacy | Not applicable            |  |
| Integrity           | No failure at 124 minutes |  |
| Insulation          | 46 minutes                |  |

## 6. Photos

#### 6.1 Photos before the test




Figure 1 – Exposed face prior to test commencement




Figure 2 – Unexposed face prior to test commencement